



Confidential

NATIONAL DEVELOPMENT COMPLEX
Deputy Directorate General of Quality Control
Plasma Smelting Laboratory-3-H

TEST REPORT

Test Report No: TR (055)/PS/22

Job Card No: JC (083)/PS/22

Date: 14-10-22

INDENTER'S DATA	
Name: Fazal Ullah	Designation: M (T)
Group & Site: Preform & 3T	Directorate: 3DC-P
Organization: NDC	Contact No: 051- 9314438, extn 209

GENERAL DATA	
Sample Name: 3D Carbon Composite	ID No: RD-19C/PS/01 (Sample1)
Lot No: 3D/CCC/Jun 21/L-09	Lot Size: -
Quantity: 01	Chemical Composition: Carbon
Test Type: General	Sample Receiving Date: 13-04-22 Test Date: 14-04-22

TEST DATA	
Test Name: Ablation Test	
Qualification Standard: MDE-MP-SQC (Rev#04)	
Standard Test Method: 1-E 458-72(Re approved 2002)	
Test Environmental Conditions: Ambient	
Test/Calorimetry Equipment & Instruments Used: Hugel Arc Heater, Digital Micrometer.	
Radiation & Optical Equipment used: Nil Enthalpy Measurement Technique: By Empirical Formula	
Flow Temperature:	2943 K
Flow Enthalpy:	3.452 MJ/Kg
Duration of Exposure:	20 Sec
Results:	▪ Test results attached (at page 02 of 02)
Remarks:	▪ These results relates only to the sample mentioned and tested above. ▪ This test report shall not be reproduced except in full, without written approval of the laboratory. ▪ The working medium for generation of Plasma Arc is air. ▪ Uncertainty in ablation rate calculation is ± 0.00774 mm/Sec at 95 % confidence level.

Test Performed By: Wasim Ahmad Zahid, GM (Elect) <i>for signature</i>	
Reviewed By: Muhammad Zahid Irfan, PD (PS) <i>Signature</i>	Contact No: 3205/3287

Approved By: Khalid Atta, Dir (STE) <i>Signature</i>	
--	--

Prepared By: FM/GM	Reviewed & Recommended By: GM/HOD	Approved By: GMR/HOD/PD
--------------------	-----------------------------------	-------------------------

PS/FM/02, Issue 20(09-07-21)