



NATIONAL DEVELOPMENT COMPLEX

Deputy Directorate General of Quality Control

Mechanical Testing Laboratory; S#3A

TEST REPORT

Signature

Test Report No: TR (181)/MTL/22
Job Card No: JC (427)/MTL/22

Date: 15-03-2022

INDENTER'S DATA		
Name: Shamim Khan Asif	Designation: FM-I	
Group: PP	Directorate/Sr.Dte/DDG: ADP/CPS	
Organization: NDC	Site: 3-C	Contact No: 3656

GENERAL DATA			
Sample Name: Silica Phenolic Ablative		Sample ID: PP-Si-10A/1120-TS-01~05 Lot # Si(820)-10A/1120-221~333	
Project ID: Misc.		Sample Material: Silica Phenolic Ablative	
Chemical Composition (If any): Not Provided			Geometrical Shape: Strips
Receiving Date: 15-03-2022	Quantity: 05 samples	Lot Size: 7922 RM (If any)	Test Date: 15-03-2022

TEST DATA			
Test : Tension	Test Type: General	Temp & Humidity: 21°C & 42%	Test Speed: 2 mm/min.
Gauge Length: Nil	Gauge Height: NA	Span: NA	Scale: NA
Instrument Used: Universal Testing Machine 100 KN			
Extensometer Used: Not used		Load Cell Used: 100 KN	
Test Method: MTL/SOP/03, MTL/WI/02 & ASTM D3039		Qualification Standard: MDE-MP-SQC (Rev 01)	
RESULTS:	Sample No.	UTS (MPa)	
	01	143.5	
	02	163.5	
	03	128.7	
	04	140.9	
	05	147.6	
Status: Samples are Qualified			
Remarks (if any):			
1. These results relate to the samples mentioned and tested above. 2. This Test Report shall not be reproduced except in full, without written approval of laboratory. 3. Qualification Criteria: UTS should be: ≥ 40 MPa.			

Test Performed By: Abid Butt; RA	Contact No. 3247
----------------------------------	------------------

Verified By: <i>Signature</i> Mubasher Hassan Khan; PD (MT)	Approved By: <i>Signature</i> Khalid Ata; Dir. (STE)
--	---

MTL/FM/02, Issue 10 (03-04-17)

End of Report

Page 1 of 1

Prepared by: GM	Reviewed by: GM/HOD	Approved by: GMR/DD
-----------------	---------------------	---------------------